


## **GENERAL PLANTING NOTES:**

- ALL INVASIVES REMOVAL, PLANTING AND SEEDING SHALL BE DONE BY VOLUNTEERS AND/OR OTHERS. EXCEPTION: PLAYFIELD GRASS SEEDING PER SPR SPEC SECTION 02937 SHALL BE DONE BY CONTRACTOR.
- 2. FOR UNDERSTORY PLANTING PLAN, INCLUDING SHRUBS & GROUND COVERS, SEE SHEET 24A.
- 3. FOR PLANTING DETAILS, SEE SHEET 25-26.
- 4. FOR PLANT MATERIALS LIST (TOTAL FOR PHASE 2 PLANTING PLAN), SEE SHEET 26.
- 5. FIELD ADJUSTMENTS OF TREE & OTHER PLANT MATERIAL LAYOUT TO MEET SPECIFIC SITE CONDITIONS ARE ANTICIPATED.
- PROVIDE VIEW CORRIDORS AS INDICATED ON THE PLAN. NO TREES OR LARGE SHRUB MASSES (MORE THAN 3 PLANTS) TALLER THAN 4 FEET MATURE HEIGHT SHALL BE PLANTED IN VIEW CORRIDORS. IN ADDITION, MAINTAIN VIEWS TO LAKE WASHINGTON & MT. RAINIER FROM GOLDMARK OVERLOOK.
- 7. ADJUST LOCATIONS OF PLANT MATERIALS TO AVOID CONFLICT WITH EXISTING PLANTS, STRUCTURES, UNDERGROUND AND OVERHEAD UTILITY LINES AND EQUIPMENT, STREAM ENHANCEMENTS AND SITE FURNISHINGS; AND TO PROVIDE FOR VISIBILITY, PEDESTRIAN SAFETY, AND CLEARANCE FROM PAVING AND STREET EDGES.
- 8. FOR INFORMATION AND COORDINATION WITH SITE WORK, STRUCTURES, AND CREEK ENHANCEMENTS, SEE GRADING & LAYOUT PLAN AND STREAM ENHANCEMENT DETAILS.
- 9. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE RESTORED AS INDICATED OR REPAIRED TO ORIGINAL OR BETTER CONDITION.
- 10. MULCH ALL PLANTING AREAS WITH MINIMUM 4" WOOD MULCH, EXCEPT WITHIN CREEK CHANNEL, FRESHWATER WETLAND OR LAKE. AFTER COMPLETION OF PLANTING AND PRIOR TO SEEDING, RE-MULCH PLANTING AREAS AS REQUIRED TO ACHIEVE 4 INCH DEPTH OF WOOD MULCH.
- 11. SEED AREAS WITH SEED MIX INDICATED. DO NOT SEED CREEK CHANNEL, FLOODPLAIN, WETLAND OR OVER OPEN WATER.



>>>CAUTION<

CALL BEFORE YOU DIG!

NOT LESS THAN TWO OR MORE THAN TEN BUSINESS DAYS

PRIOR TO COMMENCING EXCAVATION OR DEMOLITION, SECURE THE SERVICES OF A COMMERCIAL UNDERGROUND

UTILITIES LOCATOR SERVICE TO IDENTIFY BELOW-GROUND IMPROVEMENTS THAT MAY NOT BE INDICATED ON THE

DRAWINGS, FOR IRRIGATION SYSTEMS, CALL SEATTLE

PARKS PLUMBING SHOP (206 684 7070)

>>800 424 5555<<

PEDESTRIAN TRAIL MONUMENT IN CASE

CATCH BASIN FIRE HYDRANT

UTILITY POLE

REMOVE TREE

STORM DRAIN MANHOLE

PROTECT EXISTING TREE

— CONTOUR LINE

BRIDGE OVERLOOK DECK

PEDESTRIAN TRAIL, WIDTH AS NOTED


LOG WEIR OR BED CONTROL LOG



Penhallegon Associates Consulting Engineers, Inc. Kirkland, WA 98033 1-800-945-8408



<u>OR, Inc.</u>	5	
	4	
	3	
e, WA	2	
	1	
	NO.	REVISION - AS BUILT
	•	



(O)

MADRONA PARK **CREEK DAYLIGHTING** & RESTORATION

SEATTLE PARKS

ANDRECREATION

TREE
PLANTING PLAN
PHASE 2

( IN FEET )

	DESIGNED	KN/PG	DATE	4/2006
REE	DRAWN _		DESIGN	REVIEW
REE	CHECKED _	KN/PG		
ING PLAN	AN ORDINANCE NO.		CUEET	24 05
14050	CONTRACT NO.		SHEET _24_ OF	
IASE 2				24
	SCALE 1	= 20		4

All work done in accordance with the City of Seattle Standard Plans and Specifications in effect on the date shown above, and supplemented by Special Provisions.